BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the Work : Providing and filling of Pot Holes in ward no 07 Byataraynapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	2710.20	KSRRB- M 3000-2: Making up loss of Material/irregulatities on shoulder ot the design level by adding fresh approved soil and compacting it with appropriate equipment complete as per	Sqm	**21.60**	
2	**271.02**	KSRRB M400-17 : Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material of tipper to site, laying in	cum	**1713.96**	
3	**2710.20**	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous	Sqm	**370.44**	
4	300.00	Supply of Crushed Aggrigate Pg no 02 item no 41 sr 2015-16		825.00	
5	300.00	Supply of Stone Dust Pg no 02 item no 50 sr 2015-16		750.00	

ಈರದು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....( )
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

22/11

Executive Engineer 21/12
Byatarayanapura Division
BBMP, Bangalore - 92